


# High power continuous wave test of RF couplers for the RFQ of the Linear IFMIF Prototype Accelerator.



DE FRANCO Andrea for the LIPAc team

第20回日本加速器学会年会 - 29<sup>th</sup> August – 1<sup>st</sup> September 2023



Linear IFMIF Prototype Accelerator (LIPAc)

Rokkasho Fusion Institute (BA Site)

De Franco A. <sup>†</sup>, Hirosawa K., Ishimura K., Kaneko N., Kondo K., Kubo N., Masuda K., Nakayama T., Narita T., Sugimoto M., Yanagimachi T., National Institutes for Quantum Science and Technology (QST), Rokkasho, Japan

Caballero C., Gonzalez-Gallego S.C. L., Maindive L., Morales J.C., University of Granada, Granada, Spain



Garcia J. M., The Centre for Energy, Environmental and Technological Research (CIEMAT), Madrid, Spain

Gex D., Moya I., Scantamburlo F.<sup>1</sup>, Fusion for Energy (F4E)

<sup>1</sup>also at National Institute for Nuclear Physics (INFN), Legnaro, Italy




International Fusion Materials Irradiation Facility (IFMIF) will address the need of a neutron source for material tests toward future Fusion Power Plant




Linear IFMIF Prototype Accelerator (LIPAc)  
@QST in Rokkasho, Aomori, Japan  
EU-Japan Broad Approach agreement

More on LIPAc/IFMIF:  
Masuda: "Status of Linear IFMIF Prototype Accelerator in 2023" – TWSP16  
Hirosawa: "High-Power tests of repaired circulator for LIPAc RFQ" – FRP33






Beam dump  
5MeV→0.6MW  
9MeV→1.1 MW



4 of the 8 coaxial lines supplying RF to RFQ

Fisheye view of LIPAc




2D cut view of RFQ and its O-ring couplers before cooling enhancement.

Ceramic seal	O-ring	Brazed
Material	All Cu	Mostly SUS + 50 $\mu$ m Cu
Vacuum gauge	X	O
Arc sensor	Optical fibre + PD	APD on window
Antenna depth	34.86 mm	45 mm
Cooling	Loop + jacket + cold finger + forced air	Loop + around ceramic + inner conductor
Inner near window	Round near ceramic	Perpendicular near ceramic

O-ring couplers damaged during RF conditioning at high duty cycle.



Improved heat extraction design and re-installed in RFQ.

High-power test of Brazed couplers started.



Alumina window after O-ring melt. Visible O-ring debris. Cu black deposits at high filed region on ceramic and anchor.






2D cut view of RFQ and its O-ring couplers before cooling enhancement.

Ceramic seal	O-ring	Brazed
Material	All Cu	Mostly SUS + 50 $\mu$ m Cu
Vacuum gauge	X	O
Arc sensor	Optical fibre + PD	APD on window
Antenna depth	34.86 mm	45 mm
Cooling	Loop + jacket + cold finger + forced air	Loop + around ceramic + inner conductor
Inner near window	Round near ceramic	Perpendicular near ceramic

O-ring couplers damaged during RF conditioning at high duty cycle.

Improved heat extraction design and re-installed in RFQ.


High-power test of Brazed couplers started.



Alumina window after O-ring melt. Visible O-ring debris. Cu black deposits at high field region on ceramic and anchor.

Before can be used in RFQ need:

- Thermomechanical validation with forward power > 200kW in CW
- RF conditioning



Schematic view of test bench




Photo during test bench assembly




## Cooling


Loss in cavity ~12%  
 12 L/min each coupler (3 circuits)  
 55 L/min cavity cooling (4 circuits)

## Shielding

2 x 1 mm thick Pb curtain





Pb shielding around test bench.



## Instrumentation

- RGA+ Cold cathode vacuum gauge
- Arc sensor in each coupler
- 9 PT100
- 2 IR camera
- Dose counter (outside shield)
- Remote movable tuner
- Calorimetry on CPL1



Thermal simulations of cavity at CW with FWD 220kW.

## Vacuum

80 L/s TMP + scroll pump  
 72 hours baking at 100°C

1. Increase FWD to 220 kW, 10  $\mu$ s pulse width, 1 s rep. period
  2. Decrease rep. period to 10ms
  3. Elongate pulse width
- REV pulse shape + vacuum H<sub>2</sub>O splits in O and H



→ Multipacting/Plasma?



1 ms


Cavity frequency  
detuned  $\sim 30$  kHz

Rev pulse shape for different resonant frequency adjusted with tuner.






2D scan of FWD and its frequency. No overlap with flat and small on average REV.





Pareto front of REV shape and average.


Multipacting is present in any combination of FWD/frequency the system is capable to operate at. End of the test?



Example pulse shapes along the Pareto front of REV shape and average.

TRA too low to conclude on CPL2  
 CPL1 in much stricter conditions than originally intended.  
 → sufficient for design validation!


Pulse shape at 96% d.c. with at PW ~ 3.8 ms, RP = 4 ms.



Pulse shape at duty cycle = 96%

MP in cavity, not in CPL1 because:



- CPL1 T increase minimum
- Cavity tuning changes pulse shape
- No light observed at CPL1 view port
- High SEY of Al
- Cavity visual inspection after test



μSv integrated in 48hrs at 2 % d.c. with FWD ~200kW


Integrated dose at d.c. 2% FWD 200kW over 48hrs. Low dose on central stub. → X-ray from gap in cavity (no MP in CPL1)









Cu layer not well attached - melted



Cu layer on SUS input flange not well attached, RF enter gap and create loop, which further melt and deform. Heat marks on the nearby coupler are visible.



MP / Arcs , protruded and melted RF fingers



Traces of MP on cavity surface near tuner. Also, visible deformed and melted RF fingers.

RF loss on cuts for air pocket evacuation



RF loss induced heat in the cuts used for evacuation of air pocket near O-ring.




Cu layer not well attached - melted

Replace with Cu plating



Cu layer on SUS input flange not well attached, RF enter gap and create loop, which further melt and deform. Heat marks on the nearby coupler are visible.



MP / Arcs , protruded and melted RF fingers


Edges/gaps of tuner in high E region not ideal.  
Remove tuner and replace with flat lid.  
Cu plating of entire inner surface.



Traces of MP on cavity surface near tuner. Also, visible deformed and melted RF fingers.

RF loss on cuts for air pocket evacuation

Bridge gap with Cu mesh



RF loss induced heat in the cuts used for evacuation of air pocket near O-ring.

- LIPAc RFQ RF conditioning and beam commissioning towards CW ongoing.
- RF couplers identified as critical system.
- O-ring based couplers used so far were improved and re-installed
- Original coupler`s thermal design validated with a high-power high duty cycle test bench
- Bridge cavity will be improved to complete test/conditioning of the series.