

less than 100 nsec are used. Similarly the pulsed beam accelerated to 8 GeV is extracted at 60 Hz with fast kickers and bump magnets.

RF voltage is 19 MV at 8 GeV for a quantum lifetime about 10 sec, for which an RF power of 1.8 MW is fed from two 1 MW klystrons, instead of four klystrons, into 8 five-cell cavities. Meanwhile RF voltage is 8 MV or less at 1 GeV for matching to the energy spread of injected beam, for which 0.3 MW is needed. However, the dynamic range of the klystron power does not cover the above range, so the voltage variation is performed by changing the RF phases between two klystrons while keeping the power constant.

Vacuum system was reduced in the number of components. The system is pumped by 72 ion pumps (40 l/s), 10 ion pumps (400 l/s) and 19 turbo molecular pumps (50 l/s), and separated by 11 valves and additional three valves in RF section. Vacuum chamber is made of stainless steel, and expected pressure is less than 10^{-6} Torr.

Beam transport from the synchrotron to the storage ring is shown in Fig.6. The number of bending and quadrupole magnets was reduced substantially. The beam is injected from the inside of the storage ring. Total length of the transport line is about 300 m, and the level difference between the synchrotron and the storage ring is 9 m.

So far several R and D's have been performed. Model magnets of the synchrotron, bending, quadrupole, sextupole, septum and kicker magnets, were constructed, and their performance is under test. A prototype of RF system was constructed and a high power test of a five-cell cavity has been performed. A vacuum system including a vacuum chamber for a unit cell was constructed and tested.

Control system of the whole facility including the storage ring is under discussion.

Buildings and Utilities

Expected total power dissipation is 1.5 MW for the linac and 8.1 MW for the synchrotron. Electric power capacity is 3.7 MVA for the linac and 24 MVA for the synchrotron, and the capacity for the buildings of the linac and the synchrotron is 4.2 MVA. The buildings for the linac, the synchrotron and their power supplies as well as utilities are shown in Fig.7. A control room locates near the crossing point of the linac and the synchrotron, and used for both the accelerators.

Acknowledgement

Design works for the injector system have been performed by the members of JAERI group in collaboration with RIKEN group, to whom the author is obliged.




Fig.6 Beam transport from synchrotron to storage ring.




Fig.7 Buildings for injector system.